

From

To

**The Executive Engineer,
Panjab University,
Construction Office,
Chandigarh-160014.**

No. Works/.....

Dated.....

Dear Sir,

Please quote your lowest market rate for the supply of the following in a sealed cover marked on the envelope “**QUOTATION DUE ON 09.09.2022 at 3:30 P.M.,**” along with your other terms and conditions of supply, if any.

Ch. To:- Rs. 4,70,000/- Out of Infrastructure Development grant (Group-II)

Sub head:- DBT-Builder Grant

Approx. Amt.:- Rs. 4, 70, 000/-

EMD. Amt.:- Rs. 9, 400/-

S.No.	Description of items	Qty	Unit	Rate
1.	Supply of readymade prefinished wall side Modular Laboratory table of 2900mm x 675mm x 838mm in size. The table is to be made of pretreated epoxy powder coated, corrosion resistant CRCA sheet with minimum 45 to 50 micron thick coating. The table shall have 4nos. storage cabinet of 750mm long having one drawer with double swing door. The table shall have 6nos. storage cabinet of 750mm long having one drawer with double swing door, 2 nos. sink unit with 2-way goose neck tap. The storage cabinet of table shall have locking facility as per manufacturer specification. The body of cabinet shall be of 0.8mm thick CRCA sheet having sandwich construction on left hand and right hand side wall and the doors shall be of size 16mm to 18mm thick with square edges and frame to be made of 1mm thick CRCA MS sheet. The doors of cabinet/Table shall have Hydraulic steel hinges with Zero crank and for drawers telescopic channel to be used. The top of table shall be in black granite 16 to 18mm thick supported underneath with 11mm thick BWR ply.	1.00	Nos.	@Rs.....
2.	Supply of readymade prefinished wall side modular laboratory table of 2800mm x 675mm x 838mm in size. The table is to be made of pretreated epoxy powder coated, corrosion resistant CRCA sheet with minimum 45 to 50 micron thick coating. The table shall have 4nos. storage cabinet of size 750mm long having double swing door and one shelf inside the cabinet, 3no leg space of 750mm long . The body of cabinet shall be of 0.8mm thick CRCA sheet having sandwich construction on left hand and right hand side wall and doors. The door shall be of 15mm thick to be finished with 1mm thick CRCA ms sheet. The doors of cabinet/Table shall have Hydraulic steel hinges with Zero crank. The handle of shutter shall be of heavy duty PVC recessed inside the shutter. Each storage shall have cabinet and sink module to be provided with baseframe made of 30mm x 30mmx 1.2mm CRCA square pipe prefinished with nylon level adjusters. The top of table shall be finished with 16mm to 18mm thick black Granite with fully rounded of edges and corners (be approved). Underneath the stone 11mm thick BWR ply to be provided. The locking arrangement of cabinet shall be of approved brand.	1.00	Nos	@Rs.....
3.	Supply of readymade prefinished wall side modular laboratory table of	1.00.	Nos	@Rs.....

	1100mm x 675mm x 838mm in size. The table is to be made of pretreated epoxy powder coated, corrosion resistant CRCA sheet with minimum 45 to 50 micron thick coating. The table shall have 1 no. sink unit with 3-way goose neck tap. Cabinet of size 750mm long having double swing door with leg space of 750mm long. The body of cabinet shall be of 0.8mm thick CRCA sheet having sandwich construction on left hand and right hand side wall and doors. The door shall be of 15mm thick to be finished with 1mm thick CRCA ms sheet. The doors of cabinet/Table shall have Hydraulic steel hinges with Zero crank. The handle of shutter shall be of heavy duty on the shutter. Each storage shall have module to be provided with base frame made of 30mm x 30mm x 1.2mm CRCA square pipe prefinished with nylon level adjusters. The top of table shall be finished with 16mm to 18mm thick black Granite with fully rounded edges and corners (be approved). Underneath the stone 11mm thick BWR ply to be provided. The locking arrangement of cabinet shall be of approved brand.			
4.	Supply of Reagent rack on existing RCC counter of 5400 mm length to be modular design and to be provided with base frame made of 30mmx30mmx1.2 mm CRCA square pipe prefinished with nylon leveller adjusters along with 2 stage storage shelves of 300 mm depth & 680 mm height. The top of table shall be finished with 16 mm to 18 mm thick black Granite with fully rounded edges & corners. Underneath the stone 11 mm thick BWR ply to be provided. This table shall have 2 nos. socket of 5x15 amp shall be provided at bottom of rack. The drainage and water line pipe shall be as per down in accordance with position of table.	2.00	Nos.	@Rs.....

Conditions: -

1. The validity of rates must be at least two months.
2. The supply be made within 15 days of the receipt of supply order.
3. No payment will be made on the performa invoice. The payment will be made within 30 days through Registrar's office.
4. GST Number is mandatory. The firm shall mention their rates of GST if applicable; otherwise quoted rates will be considered inclusive of GST. The rate of GST or any other condition will be mentioned by the firm on its letter head separately.
5. Condition of payment in cash shall not be accepted.
6. F.O.R. P.U., Chandigarh. shall be staked at P.U., Chd including loading & unloading.
7. The copy of the GST shall be submitted by the firm along with Quotation.
8. The firm shall mention the due date of quotation on the envelope along with address of firm.
9. The firm shall mention the make of material in the quotation which to be supplied.
10. By product of any make shall not be permitted.
11. The installation will be free of cost

Executive Engineer-I,
P.U., Chandigarh